MASCALLS COURT ROAD

~ PROPOSED PUFFIN CROSSING ~

KEY:

- New footway construction.
- Topsoil and seed to new and reinstated verge and playing field areas.
- Carriageway resurfacing
- New hedgerow planting
- New 2.0m high close boarded timber fence
- New chestnut spile fencing
- New pedestrian guardrail
- New traffic signal pole
- Traffic signal feeder pillar and controller

N

Existing pedestrian guardrail

Existing zebra crossings removed.

Existing footway widened to 4.0m.

New chestnut spile fence

Pedestrian guardrail extended to new crossing location.

Replacement hedge planting.

Existing 'At Any Time' waiting restrictions

B2160 MAIDSTONE ROAD

MASCALLS COURT ROAD

Footway and crossing point removed, area topsoiled and seeded. Tree to remain.

Existing post and rail fence replaced by temporary 2.0m high close boarded fence with new hedge planting to front. Fence to remain until hedge is established.

Existing footway to be removed at old entrance point.

Tie-in to existing footway, exact location to be agreed with school.

Pedestrian guardrail extended to new crossing location.

New footway link within playing field, construction to match existing.

Existing hedgerow and trees to be removed to provide visibility on approach to crossing. Fence to be reinstated to suit and replacement hedge and tree planting provided.

New 'At Any Time' waiting restrictions on approach to new crossing

0 5 10 15 20 25 m

SCALE 1 : 250

This map is based upon Ordnance Survey material with the permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office © Crown Copyright. Unauthorised reproduction infringes Crown Copyright and may lead to prosecution or civil proceedings. 100019238. 2026